

## **PROJECT DATA SHEET**

**Project:** Hydrated Lime Storage and Dosing Plant – Murrumba Downs WWTP

**Timeframe:** February 2008

### **Project Services:**

Design, Supply, Install and Commission a Hydrated lime storage and dosing system for the Murrumba Downs Waste Water Treatment Plant:

- Two Lime Silos (20m<sup>3</sup> Capacity, Painted Mild Steel, Bin Activators)
- Three Microbatch Volumetric Feeders (MBF042A 0.3L/min – 1.3L/min)
- Four Screw Conveyors (Model TX, DN114, SS304, 5800 - 7000mm Long)
- Round FS3J24 Dust Collector and Hopper (24m<sup>2</sup> Unit)
- Silo Overfill Protection System (PRV, Control Panel, Level Sensor, Vibrator, Valves)



*"Specialists in material handling equipment for powders & granules."*